



Response Labs, LLC.
12 Colvin Avenue, Albany NY 12206
Phone (518) 482-5630 Fax (518) 482-5624
NYS DOH ELAP # 11917

PLM Bulk Asbestos Report

Client: Ambient Environmental
12 Colvin Avenue
Albany NY 12206

Client Project Number:

Project Name: Student Union Toilet Rooms
44 Pierrepont Ave. Potsdam, NY
Sampling Area: Barrington Student Union/Ground Floor

Laboratory Job Number: 1063-605
Sampled By: Mark Meehan
Collection Date: 5/23/2012
Date Received: 5/24/2012

Lab Sample #	Customer Sample #	Homogeneity	Color	% Non-Fibrous Matrix Material	Gravimetric Test			Total % of Asbestos
					% of Organics	% of Acid Soluble Inorganics	% of Residue	
9562	029-01	Homogeneous	Tan	76.5%				7.8%
Sampled Material: Fitting Insulation					Non-Asbestos Fibers	%	Asbestos Types:	
Sample Location: Large Diameter in Wet Wall					15.7% Fiber Glass	7.8%	Chrysotile	
Analyzed By: Adam C. Tucker Method: NYS ELAP 198.1								
Microscope: Olympus BH-2-214 Turn Around Time: Same Day Rush Date: 5/24/2012								
9563	029-02							NA/PS
Sampled Material: Fitting Insulation					Non-Asbestos Fibers	%	Asbestos Types:	
Sample Location: Large Diameter in Wet Wall							Not Analyzed Positive Stop	
Analyzed By: Method: Positive Stop								
Microscope: Turn Around Time: Positive Stop (198.1) Date: 5/24/2012								
9564	030-01	Homogeneous	Tan	71.7%				8.7%
Sampled Material: Fitting Insulation					Non-Asbestos Fibers	%	Asbestos Types:	
Sample Location: 1" Diameter in Wet Wall					19.6% Fiber Glass	8.7%	Chrysotile	
Analyzed By: Adam C. Tucker Method: NYS ELAP 198.1								
Microscope: Olympus BH-2-214 Turn Around Time: Same Day Rush Date: 5/24/2012								
9565	030-02							NA/PS
Sampled Material: Fitting Insulation					Non-Asbestos Fibers	%	Asbestos Types:	
Sample Location: 1" Diameter in Wet Wall							Not Analyzed Positive Stop	
Analyzed By: Method: Positive Stop								
Microscope: Turn Around Time: Positive Stop (198.1) Date: 5/24/2012								

Definitions of Abbreviations: NOB: Non-Organically Bound, Trace: Asbestos Detected at 1% or Less, TEM: Transmission Electron Microscope, Inc.: Inconclusive, NAD: No Asbestos Detected, NA/PS: Not Analyzed Positive Stop, NA: Not Analyzed, NVA: No Visual Asbestos

Disclaimer: PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. No Asbestos Detected or Trace results by PLM 198.6 are considered inconclusive, TEM is currently the only method that can be used to determine if materials can be considered as non asbestos containing in NY State. This report cannot be reproduced except in full without the approval of Response Labs, LLC. This PLM report relates ONLY to the items tested. Liability is limited to the cost of analysis. ELAP PLM Method 198.1 for friable samples or 198.6 for NOB Samples.

Comments:

Laboratory Director,

Justin Adams



Response Labs, LLC.
12 Colvin Avenue, Albany NY 12206
Phone (518) 482-5630 Fax (518) 482-5624
NYS DOH ELAP # 11917

PLM Bulk Asbestos Report

Project Name: Student Union Toilet Rooms
44 Pierrepont Ave. Potsdam, NY
Sampling Area: Barrington Student Union/Ground Floor

Laboratory Job Number: 1063-605
Sampled By: Mark Meehan
Collection Date: 5/23/2012
Date Received: 5/24/2012

Lab Sample #	Customer Sample #	Homogeneity	Color	% Non-Fibrous Matrix Material	Gravimetric Test			Total % of Asbestos
					% of Organics	% of Acid Soluble Inorganics	% of Residue	
9566	030-03							NA/PS
Sampled Material: Fitting Insulation					Non-Asbestos Fibers	%	Asbestos Types:	
Sample Location: 1" Diameter-Debris in Wet Wall							Not Analyzed Positive Stop	
Analyzed By:					Method: Positive Stop			
Microscope:					Turn Around Time: Positive Stop (198.1) Date: 5/24/2012			
9567	031-01	Homogeneous	Grey	60%				NAD
Sampled Material: Fitting Insulation					Non-Asbestos Fibers	%	Asbestos Types:	
Sample Location: Above Ceiling at Access Panel					40% Fiber Glass		No Asbestos Detected	
Analyzed By: Adam C. Tucker					Method: NYS ELAP 198.1			
Microscope: Olympus BH-2-214					Turn Around Time: Same Day Rush Date: 5/24/2012			
9568	031-02	Homogeneous	Grey	60%				NAD
Sampled Material: Fitting Insulation					Non-Asbestos Fibers	%	Asbestos Types:	
Sample Location: Above Ceiling at Access Panel					40% Fiber Glass		No Asbestos Detected	
Analyzed By: Adam C. Tucker					Method: NYS ELAP 198.1			
Microscope: Olympus BH-2-214					Turn Around Time: Same Day Rush Date: 5/24/2012			

Definitions of Abbreviations: NOB: Non-Organically Bound, Trace: Asbestos Detected at 1% or Less, TEM: Transmission Electron Microscope, Inc.: Inconclusive, NAD: No Asbestos Detected, NA/PS: Not Analyzed Positive Stop, NA: Not Analyzed, NVA: No Visual Asbestos

Disclaimer: PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. No Asbestos Detected or Trace results by PLM 198.6 are considered inconclusive. TEM is currently the only method that can be used to determine if materials can be considered as non asbestos containing in NY State. This report cannot be reproduced except in full without the approval of Response Labs, LLC. This PLM report relates ONLY to the items tested. Liability is limited to the cost of analysis.

Comments:

Laboratory Director,

Justin Adams

PROJECT INFORMATION

1. Client: SUNY POSTDAM		2. Project Name: STUDENT UNION TOILET ROOMS		2a. Project Address: 440 BIRCHMOUNT AVE, POSTDAM		2b. Client Contact:	
3. Project Number:		3a. Task Number: —		4. Inspector: MARZ MEEHAN		5. Collection Date: 05/23/12	
6. Sample TAT: ☐ 24 HR ☐ 48 HR ☐ 72 HR ☐ 5 Day ☐ Other RUSH		7. Building Name: BATTLINGSTON STUDENT UNION		8. Sampling Areas: GROUND FLOOR TOILET ROOMS		9. Comments: (Field) ☒ Analyze to First Positive By Homogeneous Material ☐ For Negative NOB PLM's, continue to TEM	

TYPE OF MATERIALS

[illegible]

CHAIN OF CUSTODY

20. Requiring signed By:	21. Date	22. Time	23. Received By:	24. Date	25. Time
I. <i>[Signature]</i>			<i>[Signature]</i>	9/24/12	925
II					
III					

LAB INFORMATION

26. Lab Name: <u>Leptospire, both</u>	27. Date	28. Time
a. Analyzed By:		
b. QC by:		
c. Lab Batch #: <u>1063 - 605</u>		

29. Ambient Project Manager: <i>Della V</i>	30. Results To: <i>JESSICA</i> Phone #: <i>444-2222</i> Fax: _____	31. Drawings: ☐ Sample Locations ☐ Material Locations
--	--	--

32. Comments: